

15-163-02279-00-00

KANSAS
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

JUN 29 1959

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

[Handwritten signature]
6/29/59

File No. 46-37 County: Rooks

Location: SE SE NW Sec. 6 Twp. 9 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 3400

I have this date completed supervision of plugging of:

Lease Name: Gouldman Well No. 2

Operator's Full Name: Petroleum Inc

Complete Address: R# 2 Great Bend, Kans

Plugging Contractor: Morgan Well Plugging Service

Address: Hutchinson, Kans License No. 43

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 10AM Day 23 Month 6 Year 59

The above well was plugged as follows:

8 5/8" at 202' circulated with cement - 5 1/2" 3396' with 100 sax cement.
Perforated 3353' - filled with sand to 3340', set 4 sax cement with dump
bailer, pulled 2450' 5 1/2" to 570', circulated hole with heavy mud through
5 1/2" (26 sax Gel), displaced 20 sax cement through 5 1/2" at 570', heavy
mud to 180', displaced 20 sax cement through 5 1/2" at 180', heavy mud
to 35', set bridge and 10 sax cement to bottom cellar.
Mudding and cementing by Globe Cementing Co.

Signed: *[Signature]*
Conservation Division Agent

Reviewed: *[Signature]*
Field Supervisor

Remarks:

PLUGGING
FILE SEC 6 T. 9 R. 17W
BOOK PAGE 46 LINE 37