

15-163-02840-00-00

KANSAS
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

JUN 29 1959

CONSERVATION DIVISION
Wichita, Kansas

6/29/59

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: _____ Rooks _____

Location: NW SE NW Sec. 6 Twp. 9 Rge. 17 (E) (W) _____

Name of Field: _____ Total Depth: 3422

I have this date completed supervision of plugging of:

Lease Name: Garvert Well No. B-1

Operator's Full Name: Murfin Drg Co

Complete Address: 617 Union Center Wichita, Kans

Plugging Contractor: Ace Pipe Pulling Co

Address: Great Bend, Kans License No. 2

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A x

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No x

If yes how long? _____ Reason: _____

Operation Completed: Hour 4PM Day 23 Month 6 Year 59

The above well was plugged as follows:

8 5/8" at 178' circulated with cement - 5 1/2" 3401 with 50 sax cement.

Filled with sand to 3390', set 4 sax cement with dump bailer, pulled

2700' 5 1/2" to 600', circulated hole with heavy mud through 5 1/2" (cell),

displaced 20 sax cement through 5 1/2" at 600', heavy mud to 150', displaced

20 sax cement through 5 1/2" at 150', heavy mud to 35', set bridge and 10

sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

PLUGGING
FILE SEC 6 T 9 R 17 W
BOOK PAGE 1 LINE 14