

15-162-03822-08-07

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION CE $\frac{1}{2}$  SE SE

SEC. 6 TWP. 9 RGE. 17 *W*

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Moos

Operator West Supply Co Address Chase, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3406 ~~3391~~ Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 92' circulated with cement - 4 1/2" at 3391

Lane Wells plugs at 2945' top perf 2925' - filled with sand

to 2900' set 3 sax cement with dump bailer - set 1 sack

calseal at 2792 - set 1 sack calseal at 2300' - pulled 700'

4 1/2", filled hole with mud to 150', set bridge and 15 sax cement,

mud to 35', set rock and 10 sax cement to bottom cellar.

**PLUGGING** 170  
**RECEIVED**  
STATE CORPORATION COMMISSION  
FILE SEC 6 TWP 9  
BOOK PAGE 18 LINE 5

MAY 22 1952

CONSERVATION DIVISION  
Wichita, Kansas

*5/22/52*

*[Signature]*  
District Conservation Agent

Date 5-19-52

*[Handwritten mark]*