

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 104-4
LOCATION CE¹/₂ SE SE
~~SE SE SE SE~~
SEC. 11 TWP. 9 RGE. 17

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Westhusin
Operator Plainstock Oil Co Address Box 463 Plainville, Kans
Field _____ County Rooks
Total Depth 3325 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 105' circulated with cement - 4 1/2" at 3170' to 3325
5 1/2" set at 3190' with 125 sax cement behind.
Filled with sand and cement to 3015', set 4 sax cement with
dump bailer at 3015' - pulled 1586' 5 1/2" - filled with mud
to 175', set rock and 15 sax cement, mud to 35', set rock
and 10 sax cement to bttom cellar.

PLUGGING
FILE SEC 11 T 9 R 17
BOOK PAGE 104 LINE 4

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1953
6-17-1953
CONSERVATION DIVISION
Wichita, Kansas

[Signature]
District Conservation Agent
Date 6-12-53