

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 121-11 County: Rooks

Location: NW NE SE Sec. 11 Twp. 9 Rge. 17 (E) (W)

Name of Field: _____ Total Depth: 3414

I have this date completed supervision of plugging of:

Lease Name: Westhusin A^{KCC} 2AP Well No. A-1

Operator's Full Name: Frank J. Black

Complete Address: Box 150 Mc Pherson, Kans

Plugging Contractor: R & D Casing Pulling

Address: Ellinwood, Kans License No. 236

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No _____

If yes how long? _____ Reason: _____

Operation Completed: Hour 7PM Day 26 Month 8 Year 8 58

The above well was plugged as follows:

10" at 102' circulated with cement - 5 1/2" 3408' with 100 sax cement behind.

Filled with sand to 3400', set 4 sax cement with dump bailer, pulled 2685' 5 1/2" to 600', circulated hole with heavy mud through 5 1/2" (55 sax Gel), displaced 20 sax cement through 5 1/2" at 600', heavy mud to 160', displaced 20 sax cement through 5 1/2" at 160', heavy mud to 30', set rock and 10 sax cement to bottom cellar.

Mudding and Cementing by Sun Cementing Co.

Signed: *Edson Leety*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

PLUGGING
FILE SEC 11 T 9 R 17W
BOOK PAGE 121 LINE 11

RECEIVED
STATE CORPORATION COMMISSION
9-4-1958
SEP 4 1958
CONSERVATION DIVISION
Wichita, Kansas