

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

JAN 31 1964  
1-31-1964  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Cooperative Ref Assn

Complete Address: Drawer ( C ) Great Bend, Kansas

Lease Name Westhusin Well No. 9

Location NE SW SE Sec. all Twp. 9 Rge. (E) (W) 17

County Rooks Total Depth 3467

Abandoned Oil Well x Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Halliburton Cementing Co

Address: Hays, Kans License No.

Operation Completed: Hour 5PM Day 28 Month 1 Year 64

The Above well was plugged as follows:

8 5/8" 208' circulated with cement - 5 1/2" 3465' top cement 3100'  
5 1/2" squeezed at 608' with 200 sax cement - PB with Baker plugs  
3415 & 3170'-

Rotary tools went out of 5 1/2" at 1300' on attempted clean out - lost  
scraper - 2 drill collars and 2 jts 2 1/2" drill pipe in hole at 1300'  
cut off 2 1/2" at 1145' - circulated hole with heavy gel mud - displaced  
60 sax cement through 2 1/2" at 1145' - mud to 580' - displaced 20 sax  
cement through 2 1/2" at 580' - heavy mud to 140' - 20 sax cement  
displaced through 2 1/2" at 140', heavy mud to 25' - cement to 0'-  
Pumped 14 sax gel mud between 8 5/8" and 5 1/2" at 300# pump pressure -  
no pipe recovery.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: *Leon Peety*  
Well Plugging Supervisor

DATE 1/31/64  
INV. NO. 8569-W