

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
4-14-1972
APR 14 1972

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Terra Resources, Inc.

Complete Address Drawer "C" Great Bend, Kansas 67530

Lease Name Westhusin "F" Well No. 1

Location SW SE NE Sec. 11 Twp. 9 Rge. (E) (W) 17

County Rooks Total Depth 3426'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Plugging

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 9:30 A Day 13 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3426' 8 5/8 csg set at 252' cwc: 225 sk. Cmt. Mat. 50-50 poz cmt W6% gel.

4 1/2 csg set at 3411' W/377 cu ft cmt.

4 1/2 csg PFTD 3377' and perf. (3165-3361)

Filled 4 1/2 csg W/sd (3090-3377) Dumped 4 sk cmt W/dump bailer. (3043-3090)

Cutoff and recovered 2192' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/500 lbs hulls -70 sk cmt -8 sk gel &

water -released 8 5/8 plug and pumped 50 sk cmt. PP 200 lbs -SI pres. 150 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Messing
Well Plugging Supervisor

INVOICED

DATE 4/17/72
INV. NO. 5569-W