

15-163-20278-00-00

KANSAS

Form CP-3
Rev. 6-4-68

Y

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 15 1969
CONSERVATION DIVISION
Wichita, Kansas

12/15/69

Operator's Full Name Tilco, Et al

Complete Address 200 Sutton Place, Wichita, Kansas

Lease Name Becker "A" Well No. 1

Location SE SE NE Sec. 34 Twp. 9 Rge. (E) (W) 16

County Rooks Total Depth 3421

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Leben Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 4P Day 14 Month 12 Year 1969

The above well was plugged as follows:

RTD 3421' 8 5/8 csg set at 249' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Law Messing
Well Plugging Supervisor

DATE 12/15/69

INV. NO. 1049-W