

15-163-00969-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NW NW NE

SEC. 7 TWP. 9 RGE. 17W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease _____ Fischer _____

Operator V. D. Sidey Oil Co Address Russell, Kans

Field _____ County Rooks

Total Depth 3395 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 102' circulated with cement - 5 1/2" at 3393' with
100 sax cement behind.

Filled with sand to 3390', set 4 sax cement with dump bailer,
pulled 2567' 5 1/2" - pumped hole full mud (30 sax Gel) pumped

cementing plug to 165', followed by 50 sax cement. Cement 165' to 0'

Mudding and cementing by Halliburton Co - 300# pump pressure.

REC. STATE CORP. DIVISION

Edson Scott
District Conservation Agent
Date 2-29-56

MAR 2 - 1956
03-02-1956
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 7 T 9 R 17W
BOOK PAGE 43 LINE 9