

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

OCT 7 1975  
10-07-1975  
CONSERVATION DIVISION  
Wichita, Kansas

15-163-20581-00-00

Operator's Full Name Gusher, Inc., c/o Everett Sechtem

Complete Address 822 West 21st St., Kearny, Nebraska

Lease Name Fisher Well No. 1

Location 100' E of NW NW NE Sec. 7 Twp. 9 Rge. (E) (W) 17

County Rooks Total Depth 3403

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 4:30 A Day 3 Month 9/10 Year 1975

The above well was plugged as follows:

RTD 3403' 8 5/8 csg set 212' cwc 150 sk. Plg. Mat. 50-50 poz cem 2% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 500' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Rev. M. M. M...  
Well Plugging Supervisor

DATE 10-8-75

INV. NO. 2022-4