

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

MAR 27 1967
03-27-1967
CONSERVATION DIVISION
Wichita, Kansas

15-163-20012-00-00

Operator's Full Name Hollar Oil Company

Complete Address: 1117 Plaza Building Wichita, Kansas

Lease Name Hrabe Well No. 1

Location SW NW NE Sec. 8 Twp. 9 Rge. 17 (E) (W) X

County Rooks Total Depth 3142

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Shields Drilling Co.

Address: Russell, Kansas License No.

Operation Completed: Hour 6:45 P Day 24 Month 3 Year 1967

The Above well was plugged as follows:

RTD 3142' 8 5/8 csg set at 164' cwc.

Gunned pits, circulated heavy mud, set cementing plug at 480' and displaced 20 sc cem. thru drill pipe. Heavy mud to 160' set cementing plug and displaced 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 3/27/67

INV. NO. 4961-W