

KANSAS

Form CP-3  
Rev. 6-4-68

f

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENCY'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-163-01493-0600 (of this well)

Operator's Full Name Southern States Oil Company

Complete Address P. O. Box 1365, Great Bend, Kansas 67530

Lease Name Thompson Well No. 5

Location NW NW SE Sec. 9 Twp. 9 Rge. (E) (W) 17

County Rooks Total Depth 3496'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 12 N Day 13 Month 1 Year 1978

The above well was plugged as follows:

RECEIVED  
STATE CORPORATION COMMISSION

Total Depth 3496' 8 5/8 csg set 197' cwc 170 sk.

JAN 16 1978  
1/10/78

5 1/2 csg set 3487' cw 150 sk cem.

CONSERVATION DIVISION  
Wichita, Kansas

5 1/2 csg sq. at 2366' W/100 sk cem.

27 jts tbg sanded in. top of sand 1836'. Dumped 3 sk cem. W/dump bailer.

Cutoff & recovered 610' of 5 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 15 sk gel & water with

300 lbs hulls, followed with 70 sk 50-50 poz 6% -displaced with 7 sk gel & water-

& capped with cementing plug & 50 sk 50-50 poz 6% & shut in. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Massey  
Well Plugging Supervisor

INVOICED

DATE 1-17-78

INV. NO. 6591-u