

15-163-02808-50-50

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SE SE NW

SEC. 9 TWP. 9 RGE. 17

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. B-1 Lease Mainquist

Operator Osage Oil & Gas Address 709 Pet Bldg Wichita, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3520 Feet.

Plugging Contractor Sierra Pet Inc

Plugging Contractor's License No. \_\_\_\_\_

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 182' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at

600', displaced 20 sax cement through drill pipe, heavy mud to

175', set cementing plug and displaced 15 sax cement through drill

pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10

sax cement to bottom cellar.

*Edwin Betty*

District Conservation Agent

Date 10-5-57

RECEIVED  
OCT 9 1957  
CONSERVATION DIVISION  
Wichita, Kansas

10/9/57

PLUGGING  
FILE SEC. 9 T. 9 R. 17W  
BOOK PAGE 51 LINE 28