

15-163-02809-00-01

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 1962
CONSERVATION DIVISION
Wichita, Kansas

3/6/62

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks

Location: NE NE SW Sec. 9 Twp. 9 Rge. _____ (E) _____ (W) 17

Name of Field: _____ Total Depth: 3501

I have this date completed supervision of plugging of:

Lease Name: Fike Well No. 2

Operator's Full Name: Morganstern-Specter

Complete Address: Box 661 Russell, Kansas

Plugging Contractor Knight Casing Pulling

Address: Chase, Kansas License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 27 Month 2 Year 62

The above well was plugged as follows:

8 5/8" 279' circulated with cement - 4 1/2" 3496' with 125 sax cement.
Filled with sand to 3480', set 3 sax cement with dump bailer - pulled 2280'
4 1/2" to 550', circulated hole with heavy gel mud (25 sax), through 4 1/2"
displaced 20 sax cement through 4 1/2" at 550', heavy mud to 180', displaced
20 sax cement through 4 1/2" at 180', heavy mud to 35', filled with cement to
bottom cellar.

Mudding and cementing by Knight Pump Truck.

Signed: Edson Terry
Conservation Division Agent

Reviewed: Harold H. H. H.
Field Supervisor

Remarks:

INVOICED
DATE 3/16/62
INV. NO. 4645-u