

15-163-03343-00-00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 87-10

LOCATION SE SE SW

SEC. 9 TWP. 9 RGE. 17

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease _____ Fike _____

Operator Alkay Oil Co Address 929 Kennedy Bldg Tulsa, Okla

Field _____ County Rooks

Total Depth 3437 Feet.

(Describe briefly the manner in which the well was plugged)

10" at 160' circulated with cement - 5" at 3235' with 150

sax cement behind - approx 575' 2 1/2" tubing and rods left

in hole - Sand broke in and filled hole with sand to 2880'.

Pulled approx 700' of 7" casing - filled with mud to 160',

set rock and 20 sax cement - mud to 35', set rock and 10 sax

cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAY 25 1953

CONSERVATION DIVISION
Wichita, Kansas

Edson Petty
District Conservation Agent

Date 5-14-53

PLUGGING

FILE SEC 9 T 9 R 17W
BOOK PAGE 87 LINE 10