

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 7 1973  
05-07-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-163-20487-00-00

Operator's Full Name Dreiling Oil Company  
Complete Address R. R. # 2 Victoria, Kansas  
Lease Name Lambert Well No. 1  
Location SE SE SW Sec. 14 Twp. 9 Rge. (E) (W) 20  
County Rooks Total Depth 3745'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor        Co. Tools         
Address        License No.         
Operation Completed: Hour 5:30 A Day 6 Month 5 Year 1973

The above well was plugged as follows:

RTD 3745' 8 5/8 csg set at 207' cwc 150 sk. Cmt. Mat. 50-50 poz W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 700' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar/

I hereby certify that the above well was plugged as herein stated.

Signed: Res J. Massey  
Well Plugging Supervisor

INVOICED  
DATE 5-9-73  
INV. NO. 7335-10