

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-163- 2/ 328-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Liberty Enterprises, Inc.

Complete Address 308 W. Mill - Plainville, Kansas 67663

Lease Name Lambert Well No. 1

Location NE-NE-NE Sec. 16 Twp. 9 Rge. 20 (East) (West)

County Rooks Total Depth 3754

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing - Box 176

Address Chase, Kansas 67524 License No. 683

Operation Completed: Hour: 11:30A Day: 1 Month: Feb. Year: 19 82

Plugging Operations attended by Agent?: All X Part None

The above well was plugged as follows:

8 5/8" set @ 250' w/145 sk cement - 4 1/2" @ 3750' w/150 sk.
Top perms - 3485' - Plug back 3400 w/50' sand & 5 sk cmt.
Ordered 140 sk 4% gel, 3% CA-Cl, 20 sk gel - 5 sk hulls & 8 5/8" Plug.
Pumped in 3 sk hulls - 12 S. gel - 2 S. hulls - 70 sk cmt -
8 S. gel - Red plug - 70 sk cmt.

MAX. PSI, 700[#] (cmt. by Allis)

Amount of Surface Casing: 250'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

FEB - 9 1982
02-09-1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICE
2-11-82
9394-W