

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

15-163-00425-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 66-41

LOCATION NE SW SW (?)

SEC. 17 TWP. 9 RGE. 20

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Phannensteil

Operator Anschutz Drg Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 3908 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 199' circulated with cement - 5 1/2" at 3908' with
100 sax cement behind - perforated at 3810'.

Filled with chat to 3800', set 4 sax cement with dump bailer,
pulled 3100' 5 1/2" - filled with mud to 199', set rock and 15 sax
cement - mud to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

FEB 25 1953
02-25-1953
CONSERVATION DIVISION
Wichita, Kansas

Edward J. ...
District Conservation Agent
2-23-53

Date _____

PLUGGING
FILE SEC 17 T 9 R 20
BOOK PAGE 66 LINE 41