

2

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

MAY 23 1977
05-23-1977
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163- 20,686-00-00 (of this well)

Operator's Full Name Liberty Enterprises, Inc.

Complete Address 308 W. Mill, Plainville, Kansas

Lease Name Simoneau Well No. 1

Location NW SW NW Sec. 17 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth 3826'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Helberg Drlg.

Address Morland, Kansas License No.

Operation Completed: Hour 4:45 P Day 18 Month 5 Year 1977

The above well was plugged as follows:

RTD 3826' 8 5/8 csg set 209' cwc 150 sx. Plg. Mat. 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 850' thru drill pipe.

Heavy mud to 200' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 5-24-77

INV. NO. 5212-W