

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-163-21,746-50-R

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Wm. A. Spivey

Complete Address 120 W. 35th, Hays, Mo. 67601

Lease Name Simoneau Well No. 2 20

Location SE SE NW Sec. 17 Twp. 9 Rge. 12 (East) (West)

County Rooks Total Depth 3925'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Helberg Oil Co.

Address Box 32, Morland, Mo. 67650 License No. _____

Operation Completed: Hour: 1:30 PM Day: 6 Month: 8 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 208' SP. cnc. w/ 35 sacks common - 2% Gel. - 3% Cal. Cl.

Ordered 140 sacks 50 pos mix - 4% Gel. - 3% Cal. Cl. + 8 5/8" plug spot w/ drill stem w/ heavy mud between all plugs.

1st plug @ 960' w/ 80 sacks

2nd plug @ 250' w/ 40 sacks

3rd plug - solid bridge of hulls + plug @ 40' w/ 10 sacks

Circulate 10 sacks in rat hole

Amount of Surface Casing: 208' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

[Large handwritten signature]

Signed: _____
Conservation Division Agent

STATE CORPORATION COMMISSION
RECEIVED
AUG 24 1982
CONSERVATION DIVISION
Wichita, Kansas
RECEIVED
AUG 24 1982
CONSERVATION DIVISION
Wichita, Kansas

INVOICE

DATE 9-8-82

INV. NO. 1055-W