

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 1 1967
02-01-1967
CONSERVATION DIVISION
Wichita, Kansas

15-163-20003
39-00-00

Operator's Full Name Robert H. Price

Complete Address: 5727 East 43 rd Street Tulsa, Oklahoma

Lease Name Steeples Well No. 1

Location SE SE NW Sec. 22 Twp. 9 Rge. 20 (E) (W) X

County Rooks Total Depth 3825'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: B-B Drilling Co. Inc.,

Address: Wichita, Kansas License No. 598

Operation Completed: Hour 12 Noon Day 30 Month 1 Year 1967

The Above well was plugged as follows:

RTD 3825' 8 5/8 csg set at 258' cwc 165 sc.
Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 25 sc cem.
thru drill pipe. Heavy mud to 250' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 2/1/67
INV. NO. 4694-W