

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 163-20,329-00-00 (of this well)

Operator's Full Name JOHN O. FARMER INC.

Complete Address P.O. BOX 352 RUSSELL, KANS. 67665

Lease Name STEEPLES Well No. #1

Location NE-NE-NW Sec. 23 Twp. 9 Rge. 20 (E) (W) W

County ROOKS Total Depth 3733 FE

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor JOHN O. FARMER INC + ALLIED CNT. CO.

Address P.O. BOX 352 RUSSELL, KANS. License No.     

Operation Completed: Hour 10:40 AM Day 21<sup>st</sup> Month JULY Year 1980

The above well was plugged as follows:

8 5/8" 200 FE SP. CLK 1/30<sup>st</sup> CMT. + 5 1/2" SET AT 3730 FE

PERIS - 3700-03<sup>FE</sup> - 3436<sup>FE</sup> - 39 - SQUEEZED @ 1679 1/475<sup>st</sup> CMT.

NO PIPE RECOVERY.

ORDERED 170<sup>st</sup> 50/50 Pozmix 6% GEL + 20<sup>st</sup> GEL + 76<sup>st</sup> HULL'S + 5 1/2" PLUG.

PUMPED IN WITH PUMP TRUCK.

PUT IN - 3<sup>st</sup> HULL'S + 35<sup>st</sup> CMT. + 20<sup>st</sup> GEL + 2<sup>st</sup> HULL'S

RELEASED PLUG. AND 100<sup>st</sup> CMT. MAX. PRESSURE - 700<sup>PSI</sup>.

PUMPED IN ANNULUS - 2<sup>st</sup> HULL'S + 35<sup>st</sup> CMT. - MAX PRESSURE 300<sup>PSI</sup>

I hereby certify that the above well was plugged as herein stated. (CEMENTED BY ALLIED CNT.)

RECEIVED  
INVOICED  
DATE 7-22-80 JUL 22 1980  
INV. NO. 2646-60 CONSERVATION DIVISION  
Wichita, Kansas

Signed: [Signature]  
Well Plugging Supervisor