

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-20384-00-00

RECEIVED
STATE CORPORATION COMMISSION

AUG 9 1971

CONSERVATION DIVISION
Wichita, Kansas

08-09-1971

Operator's Full Name I. O. Miller Oil Company

Complete Address 619 Brown Bldg., Wichita, Kansas

Lease Name Miller Well No. 1

Location NW NE SE Sec. 24 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth 3629'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other wells as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 2:15 A Day 4 Month 8 Year 1971

The above well was plugged as follows:

RTD 3629' 8 5/8 csg set at 209' cwc 160 sk. Cmt./ Mat. 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 190' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 8-10-71

INV. NO. 4119-W