

KANSAS
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

APR 5 1961
04-05-1961
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-163-00804-00-00

File No. _____ County: Rooks

Location: SE NW SE Sec. 25 Twp. 9 Rge. 20 (E) (W)

Name of Field: _____ Total Depth: 3791

I have this date completed supervision of plugging of:

Lease Name: Steeple G^{KC} ~~ZAY~~ Well No. G-1

Operator's Full Name: Davis Bros

Complete Address: 5 1/2 E 3rd Tulsa, Oklahoma

Plugging Contractor: Transit Corp

Address: Oklahoma City, Okla License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 9AM Day 27 Month 3 Year 61

The above well was plugged as follows:

8 5/8" 219' circulated with cement.
Circulated hole with heavy mud, set cementing plug at 550', displaced
20 sax cement through drill pipe at 550', heavy mud to 180', set plug
and displaced 20 sax cement through drill pipe, heavy mud to 40', set
plug, 1/2 sack hulls and 10 sax cement to bottom cellar.

Signed: Edon Lacey
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED
DATE 4/14/61
INV. NO. 2921-w