

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

15-163-00447-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 47-6
LOCATION NW NW SE
SEC. 25 TWP. 9 RGE. 20

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Steeples

Operator Anschutz Drg Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 3803 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 217' circulated with cement - 5 1/2" at 3735 with
75 sax cement behind and perforated and squeezed with 925
additional sax cement - P.B. Lane Wells plugs 3700' top
perforations at 3628'.

Chat to 3600', set 4 sax cement with dump bailer, pulled
2900' 5 1/2", filled with mud to 35', set rock and 10 sax
cement to bottom cellar.

PLUGGING
FILE SEC 25 T 9 R 20
BOOK PAGE 17 LINE 6

RECEIVED
STATE CORPORATION COMMISSION
OCT 10 1952
10-10-1952
CONSERVATION DIVISION
Wichita, Kansas

Edward Kelly
District Conservation Agent

Date 10-7-52