

15-163-00836-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Rocks _____ County. Sec. 2 Twp. 9S Rge. 20W (E) _____ (W)

Location as "NE/CNW&SW" or footage from lines SW SW SW

Lease Owner Murfin Drilling Company

Lease Name Baldwin Well No. 1

Office Address 507 Union Nat'l. Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-24 19 55

Application for plugging filed 8-24 19 55

Application for plugging approved 8-24 19 55

Plugging commenced 8-24 19 55

Plugging completed 8-24 19 55

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Horner, Great Bend, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3640 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	199'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st. plug w/1/2 sack hulls, 20 cement; filled hole to 35'.

Set 2nd plug w/1/2 sack hulls, 10 cement, to bottom cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Company

Address 507 Union Nat'l. Bank Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

W. R. Murfin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W R Murfin

(Address) _____

SUBSCRIBED AND SWORN TO before me this 27th day of October, 19 55.

My commission expires 6-13-59

Mabel H. Belote
Notary Public.

RECEIVED
CORPORATION COMMISSION

OCT 23 1955 10-28-55

CONSERVATION DIVISION
Wichita, Kansas



PLUGGING
FILE SEC 2 T 9 R 20W
BOOK 145 LINE 8

WELL LOG

15-163-00836-00-00

COMPANY **Murfin Drilling Company**


SEC. 2 T. 9S R. 20W

FARM **Baldwin** NO. 1

LOC. SW SW SW

TOTAL DEPTH **3640'**
COMM. **8-13-55** COMP. **8-24-55**
SHOT OR TREATED
CONTRACTOR **Murfin Drlg. Company**
ISSUED

COUNTY **Rooks**
KANSAS



CASING

20 10
15 8 5/8" @ 199 w/125 sx.
12 6
13 5

ELEVATION **2103 KB**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

20	Sand
65	Shale, sand
180	Shale
650	Shale, shells
715	Sand
1000	Shale, sand, shells
1130	Shale, shells
1286	Sand
1380	Shale, sand
1533	Shale, red bed
1599	Red bed, shale
1640	Anhydrite
1945	Shale, shells
1995	Salt, shale
2195	Shale, lime, shells
2310	Shale, lime
2425	Lime, shale
3080	Shale, lime
3315	Lime, shale
3350	Shale, lime
3385	Lime
3640	Lime, shale
3640	RTD

Tops:	
Anhydrite	1599'
Topeka	3099'
Heebner	3304'
Toronto	3326'
Douglas	3337'
Lansing-KC	3343'
B. Kansas City	3601'
Penn. basal	
congl.	3604'
Arbuckle	3619'
Total Depth	3640'

DST #1: 3410-3502, good steady blow, tool open 1 hr., rec. 1530' salt water. FP's 85 to 690#, SIP 1150# in 20 minutes.

DST #2: 3507-50, weak blow, died in 4 min., opened bypass, weak blow for 4 min., tool open 1/2 hr., rec. 20' of mud. SIP 770# in 15 min. No FP's. HP 1950#.

DST #3: 3600-25, weak blow, died in 5 min., open 1/2 hr., rec. 8' mud. Shut in 15 min. No BHP or FP's.

DST #4: 3622-40, weak blow 3 min., opened bypass at end of 20 min., packer failed, rec. 160' of mud. Shut in 15 min. No BHP or FP's.

RECEIVED
STATE CORPORATIONS COMMISSION

OCT 28 1955
CONSERVATION DIVISION
Wichita, Kansas

10-28-55

State of Kansas

County of Sedgwick

I, W. R. Murfin of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Baldwin #1 well.

PLUGGING

FILE SEC 2 T. 9 R. 20W
BOOK PAGE 45 LINE 8

Subscribed and sworn to before me this 27th day of October 19 55.

My Commission Expires: 6-13-59

W.R. Murfin

Mabel A. Belate
NOTARY PUBLIC

