


15-163-2117-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rooks County, Sec. 5 Twp. 9S Rge. 20 R/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
100' S of SW NE SW
Lease Owner K & E Petroleum
Lease Name THYFAULT Well No. 1
Office Address 816 Union Center, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Dry Hole
Date Well completed 08-21 1980
Application for plugging filed 08-21 1980
Application for plugging approved 08-21 1980
Plugging commenced 08-21 1980
Plugging completed 08-21 1980
Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3722'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

T.D. 3722'
Set 1st plug @ 900' with 70 sx.
2nd plug @ 330' with 28 sx.
3rd plug @ 40' with 10 sx.
Rathole with 5 sx., 50/50 posmix, 6% gel.

Plug was down @ 9:00 a.m. 08-21-80

RECEIVED
STATE CORPORATION COMMISSION

SEP - 2 1980

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

9-2-80

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Jack L. Partridge

801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of August, 1980

Jeanette A. Metheny
Jeanette A. Metheny Notary Public.

My commission expires 08-18-84



15-163-2117-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	K & E Petroleum, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	THYFAULT #1
LOCATION:	100' S of Sw NE SW, Section 5-9S-20W Rooks County, Kansas
SPUD DATE:	08-14-80
COMPLETION DATE:	08-21-80

0	1623	Sand & Shale
1623	1650	Anhydrite
1650	3722	Shale & Lime
	3722	Rotary Total Depth

Spud hole @ 7:30 p.m. 08-14-80. Cut 346' of a 12-1/4" hole. Ran 9 joints of new 20# 8-5/8" casing (tally 336.12'). Set @ 342.62' with 200 sx. of common cement, 2% gel, 3% c.c. Plug was down @ 4:00 a.m. 08-15-80. Cement did circulate.

T.D. 3722'. Set 1st plug @ 900' with 70 sx. 2nd plug @ 330' with 28 sx. 3rd plug @ 40' with 10 sx. Rathole with 5 sx. 50/50 posmix, 6% gel. Plug was down @ 9:00 a.m. 08-21-80.

SAMPLE TOPS:

Anhydrite	1637'
B/Anhydrite	1675'

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

RECEIVED
STATE CORPORATION COMMISSION

SEP - 2 1980

CONSERVATION DIVISION
Wichita, Kansas

9-2-80

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the THYFAULT #1, 100' S of SW NE SW, Section 5-9S-20W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 29th day of August, 1980.

Jeanette A. Metheny
Jeanette A. Metheny, Notary Public

