

15-163-20325-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rooks County, Sec. 13 Twp. 9S Rge. (E) 20 (W)

Location as "NE/CNW/SW" or footage from lines NW-SE-SE

Lease Owner Aspen Resources, Ltd.

Lease Name Steeples Well No. 1

Office Address 710 One-Twenty Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-20- 19 70

Application for plugging filed 10-21 19 70

Application for plugging approved 19

Plugging commenced 10-20 19 70

Plugging completed same 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan & Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 3593 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug to 600', 70 sacks cement thru drill pipe;
240', 25 sacks cement thru drill pipe;
40', 1/2 sack hulls, plug and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1970
CONSERVATION DIVISION
Wichita, Kansas

10-26-1970

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Aspen Drilling Co.

Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

William S. Schachle (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William S. Schachle


Great Bend, Kansas

(Address)

Subscribed and sworn to before me this 21st day of October, 1970

Theora Holleman Notary Public.

My commission expires April 18, 1972



OCT 26 1970

CONSERVATION DIVISION
Wichita, Kansas

15-143-20325-00-00

DRILLERS LOG

COMPANY:	Aspen Resources, Ltd.
CONTRACTOR:	Aspen Drilling Co.
LEASE NAME:	Steeple #1
LOCATION:	NW-SE-NE Sec. 13-T9S-R20W Rooks County, Kansas
ELEVATION:	2080 K. B.
SURFACE CASING:	6 jts. (242') 8 5/8"
COMMENCED:	October 10, 1970
COMPLETED:	October 20, 1970
ROTARY TOTAL DEPTH:	3593'

<u>FORMATION</u>	<u>DEPTH</u>	
Surface Clay & Shale	120	Ran 6 jts. (242') 8 5/8" casing
Shale	1000	set at 249' w/150 sacks.
Sand	1245	Cement circulated.
Red Bed & Shale	1510	
Anhydrite	1548	DST #1 3296-3320
Shale & Shells	1950	DST #2 3320-3364
Shale & Lime	2270	DST #3 3563-3568
Lime & Shale	2675	DST #4 (mis-run) 3567-3573
Shale & Lime	3100	DST #5 3563-3578
Lime & Shale	3262	DST #6 3563-3588
Arbuckle	3568	DST #7 3563-3593
Rotary Total Depth	3593	

D & A

AFFIDAVIT

State of Kansas)
) ss:
 County of Barton)

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

William S. Schachle

 William S. Schachle, Affiant

Subscribed and sworn to before me this 23rd day of October, 1970.

Theora Holleman

 Theora Holleman, Notary Public

My commission expires: April 18, 1972

