


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Rooks County. Sec. 16 Twp. 9S Rge. 20 (E) (W)  
Location as "NE/CNW/SW" or footage from lines. NW 1/4 NW 1/4 NW 1/4  
Lease Owner Harry Goreng, Inc.  
Lease Name Morris Well No. 1  
Office Address 400 Brown Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 23 19 52  
Application for plugging filed July 23 19 52  
Application for plugging approved July 23 19 52  
Plugging commenced July 23 19 52  
Plugging completed July 23 19 52  
Reason for abandonment of well or producing formation Commercial quantity of  
oil not found  
If a producing well is abandoned, date of last production ----- 19 -----  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 3778 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	268	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ----- feet to ----- feet for each plug set.

Filled hole with heavy rotary mud from 3778 feet to 240 feet.  
240 feet to 195 feet - set wooden plug with 15 sacks cement.  
Filled hole with heavy mud from 195 feet to 40 feet. From 40  
feet to 0 feet set wooden plug, 1/2 sack of hulls and capped with  
10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Deek, Drilling, Inc.  
Address 1006 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Clinton Engstrand (~~employee of owner~~) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clinton Engstrand  
1006 Central Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 24 day of July, 19 52

My commission expires October 29, 1954

24-2675-S 2-52-20M

Waldemar Rogers  
Notary Public.  
STATE CORPORATION COMMISSION

JUL 26 1952  
07-26-1952  
CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC 16 T 9 R 20  
PAGE 32 LINE 31

HARRY GORE  
MORRIS #1

NW NW NW Sec. 16-9S-20W  
Rooks County, Kansas

Comm: 7-10-52  
Comp: 7-23-52  
Total Depth: 3778'

15-163-00442-00-00

Casing  
8 5/8" Set @ 268'

Cement  
150 sacks

<u>FORMATION</u>	<u>DEPTH</u>
Surface clay, sand & shale	0 - 166
Sand & shale	166 - 256
Shale	256 - 268
Shale & shells	268 - 650
Shale, sand & shells	650 - 1460
Shale & shells	1460 - 1670
Lime & shale	1670 - 1855
Shale, lime & redbed	1855 - 2011
Shale & lime	2011 - 2140
Shale & lime	2140 - 2205
Shale & lime	2205 - 2305
Shale & lime	2305 - 2400
Lime & shale	2400 - 2485
Shale & lime	2485 - 2572
Lime & shale	2572 - 2652
Lime & shale	2652 - 2740
Shale & Lime	2740 - 2824
Lime	2824 - 2852
Lime & shale	2852 - 2905
Lime & shale	2905 - 3001
Lime & shale	3001 - 3073
Lime & shale	3073 - 3148
Shale & lime	3148 - 3219
Shale & broken lime	3219 - 3312
Shale & lime	3312 - 3349
Shale & lime	3349 - 3391
Shale & lime	3391 - 3420
Lime	3420 - 3436
Lime	3436 - 3466
Lime	3466 - 3497
Lime	3497 - 3534
Lime	3534 - 3568
Lime	3568 - 3601
Lime	3601 - 3635
Lime & shale	3635 - 3677
Lime	3677 - 3706
Cong.	3706 - 3726
Lime	3726 - 3772
Lime	3772 - 3778 TD

STATE OF KANSAS )  
                          ) SS.  
COUNTY OF SEDGWICK)

RECORDED  
STATE CORPORATION  
JUL 26 1952

I hereby certify that the above information is true and correct to the best of my knowledge.

CONSERVATION DIVISION  
WICHITA, KANSAS

**PLUGGING**  
317 OCT 16 9 20  
321 NE 31

*[Signature]*

Subscribed and sworn to before me this 21th day of July, 1952.

*[Signature]*  
Notary Public

My Commission Expires: 10-29-54

