



15-163-20397-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 29 1971  
CONSERVATION DIVISION  
Wichita, Kansas

11-29-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Brau of Edmiston Drlg. has this

date requested permission to plug the following described well:

Mr. Brau guarantees payment of the plugging fee.

Operator's full Name: Cecil M. Keller & Edmiston Oil Co.

Complete Address: 801 1st Nat'l Bk. Bldg., Wichita, Ks.

Lease Name: Bobbitt-Keller Well No. 1

Location: C W/2 SW SE Sec. 2 Twp. 9 Rge. (E)(W) 20

County: Rooks Total Depth 3640' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Brau was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace

70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. F. Massey  
Conservation Division Agent