



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1965
9-27-65
CONSERVATION DIVISION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Albert Unruh, of Southwest Csg. Pulling. has this

date requested permission to plug the following described well:
Skelly Oil Co.

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company,

Complete Address: Plainville, Kansas.

Lease Name: Arpin Well No. 1

Location: NE-NE-SW Sec. 5 Twp. 9 Rge. 20W (E)(W) 18


County: Rooks Total Depth 3678 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

318' -- 8 5/8" Surface pipe, cement circulated with 300 Sx.
3678' 5 1/2" Production casing cemented with 175 Sx. Well plugged
back to 3676'. Top perforations from 3536' to 3540'. Dakota
water broke in @ 1175.

Sand well back to 3520' and set 4 Sx. cement with dump bailer
Pull 5 1/2" to 600' and circulate heavy gel mud. Displace 20 Sx.
cement thru 5 1/2" @ 600'. Pull 5 1/2" to 295' and displace 20 Sx.
cement thru 5 1/2". Pull 5 1/2", set bridge @ 40' and 10 Sx. cement
to bottom of cellar.

Very truly yours,

Conservation Division Agent