



15-163-20340-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1970

CONSERVATION DIVISION
Wichita, Kansas

12-21-70

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Davis of Hellar Drlg. has this date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: Landes Exploration Co.

Complete Address: 416 Union Center Bldg., Wichita, Ks.

Lease Name: Aryin Well No. 1

Location: NE NW SW Sec. 5 Twp. 9 Rge. (E)(W) 20

County: Rooks Total Depth 3704' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Davis was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace

70 sk cmt thru drill pipe. Heavy mud to 200' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo J. Murray
Conservation Division Agent