



15-163-20286-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1970
CONSERVATION DIVISION
Wichita, Kansas
1-13-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cooke of Imperial Oil Co. has this date requested permission to plug the following described well:

Mr. Cooke guarantees payment of the plugging fee.

Operator's full Name: Hinkle Oil Co.

Complete Address: 1016 Union Center Wichita, Ks.

Lease Name: Kern "B" Well No. 3

Location: NW SE SE Sec. 10 Twp. 9 Rge. (E)(W) 20

County: Rooks Total Depth 3692 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Cooke was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 720' and displace
70 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Ben F. Marshall
Conservation Division Agent