

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

15-163-20312-00-00

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 17 1970

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

06-17-1970

Dear Sir:

Mr. Morgan of Aspen Drlg. has this

date requested permission to plug the following described well:

Mr. Morgan guarantees payment of the plugging fee.

Operator's full Name: Hinkle Oil Co.

Complete Address: 1016 Union Center Wichita, Ks.

Lease Name: Lambert Well No. 1

Location: SE SE NW Sec. 12 Twp. 9 Rge. (E)(W) 20

County: Rooks Total Depth 3647' Oil Well

Gas Well      Input Well      SWD Well      D & A XX Lost Hole     

Mr. Morgan was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace

70 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo J. Maxwell  
Conservation Division Agent