



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

15-163-21204-00-00

STATE COMMISSION

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

FEB - 9 1981  
02-09-1981  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. John Walker of Pricee Oil Co has this date requested permission to plug the following described well:

Operator's Full Name: Beren Corporation

Complete Address: 4th Financial Bldg #970 Wichita, Kans.

Lease Name: Berdona Well No. #1

Location: C-E 1/2 - E 1/2 - SW Sec. 16 Twp. 9 Rge. 20 (E) (W)

County: Rooks Total Depth: 3795 FT

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Walker was instructed to plug the well as follows:

8 5/8" 327 FT SB. CUC w/ 130<sup>ST</sup> Cement - 2% Gel - 3% Ca-Cl.  
Order 110<sup>ST</sup> 50/50 Pozmid 6% Gel + 8 5/8" Plug (Elev. 2247)  
spot with Drill Stem - With Heavy mud Between all Plugs  
1<sup>ST</sup> Plug @ 860 FT w/ 65<sup>ST</sup> Cmt.  
2<sup>ND</sup> Plug @ 300 FT w/ 30<sup>ST</sup> Cmt.  
3<sup>RD</sup> Plug -> <sup>Steel Bridge</sup> Plug @ 40<sup>FT</sup> 10<sup>ST</sup> w/ 10<sup>ST</sup> Cmt.  
5<sup>TH</sup> In Part Hole

Very truly yours, (By Sign Cmt)

Mason Schmidt  
Conservation Division Agent