



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water  
WICHITA, KANSAS 67202

15-163-20686-00-00

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 23 1977  
05-23-1977  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Helberg of Helberg Drlg. has this

date requested permission to plug the following described well:

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: Liberty Enterprises, Inc.

Complete Address: 308 W/ Mill, Plainville, Ks.

Lease Name: Simoneau Well No. 1

Location: NW SW NW Sec. 17 Twp. 9 Rge. (E)(W) 20

County: Rooks Total Depth 3 826' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Helberg was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 850' thru drill

pipe. Heavy mud to 200' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Messing  
Conservation Division Agent