

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20159-00-00

12-9-68  
RECEIVED  
STATE CORPORATION COMMISSION  
DEC 7 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Clinton Oil Company

Complete Address: 6810 West Highway 54, Wichita, Kansas 67209

Lease Name Deslogchamp Well No. 1 - V

Location NW NE NW Sec. 29 Twp. 9 Rge. 19 (E) (W) X

County Rooks Total Depth 3625

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Rains & Williamson Co., Inc.

Address: Wichita, Kansas License No.     

Operation Completed: Hour 10:45P Day 5 Month 12 Year 1968

The Above well was plugged as follows:

RTD 3625' 8 5/8 csg set at 217' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cmt.

thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey  
Well Plugging Supervisor

DATE 12/9/68

INV. NO. 8971-W