

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-163-20864-00-00 (of this well)

Operator's Full Name GRAVES DRILLING COMPANY INC

Complete Address 901 UNION CENTER - WICHITA, KANS. 67202

Lease Name THOMAS Well No. #1

Location 5 1/2 - 5 1/2 - 5 1/2 Sec. 35 Twp. 9 Rge. 19 (E) (W) W

County ROCK Total Depth 3755

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor KELSO CASING PULLING

Address BOX 176 CHASE, KANS 67524 License No. 683

Operation Completed: Hour 11:30 AM Day 19<sup>th</sup> Month MARCH Year 1980

The above well was plugged as follows:

8 5/8" 214' SD CUC w/ 175' cement. - 4 1/2 SET AT 3491' w/ 75' cement.

PERKS 3422' - 3426' - SAND BOTTOM TO 3322' AND 4' cement.

SHOT PIPE SEVERAL TIMES - RECOVERED 3111'

ON FEB 7<sup>th</sup> 1980 - PUMPED IN WITH PUMP TRUCK. - 3' HULLS' 12' GEL.

AND 22' 50' 150 P2MIX 6% GEL. - CEMENT CIRCULATED OUTSIDE SURFACE PIPE.

WASHED OUT CEMENT. - KELSO BAILED HOLE - FLUID DOWN 210'

TOP OF CEMENT. 246' - ON 19<sup>th</sup> MARCH PUT IN 8 5/8" 2 3/4 yds

OF READY MIX. CEMENTED BY ALLIED CEMENTING

AND - STOCKTON READY MIX

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 3-20-80  
INV. NO. 1771-w

Signed: Merion Schmitt  
Well Plugging Supervisor  
STATE CORPORATION COMMISSION

MAR 20 1980 3-20-80  
CONSERVATION DIVISION  
Wichita, Kansas