

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20397-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1971
CONSERVATION DIVISION
Wichita, Kansas
11-29-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Cecil Keller & Edmiston Oil Company
Complete Address 801 First National Bank Bldg., Wichita, Kansas
Lease Name Bobbitt - Keller Well No. 1
Location A/ W/2 SW SE Sec. 2 Twp. 9 Rge. (E) (W) 20
County Rooks Total Depth 3640'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 10 P Day 21 Month 11 Year 1971

The above well was plugged as follows:

RTD 3640' 8 5/8 csg set at 210' cwc Cmt. Mat. 50-50 poz W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo P. Massey
Well Plugging Supervisor

DATE 12-1-71

INV. NO. 4738-11