

40  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-19191-00-00

RECEIVED  
STATE CORPORATION COMMISSION

JUN 1 1964  
6-1-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Murfin Drilling Co & H. W. Patton  
Complete Address: 617 Union Center Wichita, Kans  
Lease Name Kellogg Well No. 1  
Location SE SW SW Sec. 4 Twp. 9 Rge. (E) (W) 20  
County Rooks Total Depth 3801  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated: \_\_\_\_\_  
Plugging Contractor: Glenn & Smith  
Address: Ellinwood, Kans License No. 396  
Operation Completed: Hour 6PM Day 26 Month 5 Year 64

The Above well, was plugged as follows:

8 5/8" 196' circulated with cement - 5 1/2" 3782' with 125 sax cement -  
Perf 3756'

Filled with sand to 3740', set 4 sax cement with dump bailer -  
pulled 1025' 5 1/2" to 550', circulated hole with heavy gel mud through  
5 1/2" - displaced 20 sax cement through 5 1/2" at 550'; heavy mud to  
200', displaced 20 sax cement through 5 1/2" at 200', heavy mud to  
35', cement 35' to 0'.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edson Perry  
Well Plugging Supervisor

DATE 6/2/64

INV. NO. 9350-W