

15-143-19192-00-00

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 5 1961

4-5-61

CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: _____ Rooks

Location: NE SW NW Sec. 4 Twp. 9 Rge. 20 (E) (W)

Name of Field: _____ Total Depth: 3900

I have this date completed supervision of plugging of:

Lease Name: Artin Well No. 1

Operator's Full Name: I. O. Miller

Complete Address: 619 Brown Bldg Wichita, Kansas

Plugging Contractor: R & D Casing Pulling Co

Address: Ellinwood, Kans License No. 236

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 11AM Day 1 Month 4 Year 61

The above well was plugged as follows:

8 5/8" 220' circulated with cement - 5 1/2" 3899' with 100 sax cement.

Perforated 3720' - filled with sand to 3700', set 4 sax cement with

dump bailer, pulled 1828' 5 1/2" to 500', circulated hole with heavy

gel mud through 5 1/2" at 500', displaced 20 sax cement through 5 1/2"

at 500', heavy mud to 160', displaced 20 sax cement through 5 1/2" at

160', heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by R & D Co pump truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE 4/28/61

INV. NO. 2987-W