

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

15-163-01035-00-00

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

SEP 27 1965  
9-27-65  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Skelly Oil Company,

Complete Address: Plainville, Kansas.

Lease Name Arpin Well No. 1

Location NE-NE-SW Sec. 5 Twp. 9 Rge. (E) (W) 10

County Rooks Total Depth 3678

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Southwest Casing Pulling, Incorporated,

Address: Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 4:00PM Day 24 Month 9 Year 1965

The Above well was plugged as follows:

318'--8 5/8" Surface pipe, cement circulated with 300 Sx.  
3678'--5 1/2" Production casing cemented with 175 Sx. Well plugged back to  
3676'. Top perforations from 3536 to 3540'. Dakota water broke in @  
1175'. Sanded well back to 3520' and set 4 Sx. cement with dump bailer.  
Pulled 5 1/2" to 540' and pumped in 18 Sx. gel. hole would not circulate.  
pulled 5 1/2" to 475' and pumped in an additional 7 Sx. gel and hole circulated.  
Displaced 20 Sx. cement thru 5 1/2" @ 475'. Pulled 5 1/2" to 295' and displaced  
20 Sx. cement thru 5 1/2". Pulled 5 1/2", set bridge @ 40' and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Nichols  
Well Plugging Supervisor

INVOICED  
DATE 9/29/65  
INV. NO. 1873-W