

af
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20340-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1970
CONSERVATION DIVISION
Wichita, Kansas

12-21-70

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Landeg Exploration Company

Complete Address: 416 Union Center Bldg., Wichita, Kansas

Lease Name Arvin Well No. 1

Location NE NW SW Sec. 5 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth 3704'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Hellar Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 7 P Day 20 Month 12 Year 1970

The Above well was plugged as follows:

RTD 3704' 8 5/8 csg set at 210' cwc Gmt. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 200' set cementing plug and displaced 20 dk cmt

thru drill pipe. Heavy mud to 40' set cementing plug. 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/21/70

INV NO 3103-W

Signed: Leo E. Massey
Well Plugging Supervisor