

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20286-0000

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1970
CONSERVATION DIVISION
Wichita, Kansas

1-13-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Hinkle Oil Company

Complete Address 1016 Union Center Wichita, Kansas

Lease Name Kern "B" Well No. 3

Location NW SE SE Sec. 10 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth 3692

Abandoned Oil Well Gas Well Input Well SWD Well D & A XXX

Other well as hereafter indicated

Plugging Contractor Imperial Oil

Address Wichita, Kansas License No.

Operation Completed: Hour 8:15A Day 9 Month 1 Year 1970

The above well was plugged as follows:

RTD 3692 8 5/8 csg set at 285' cwc Cmt. Mat. 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED
DATE 1/13/70
INV. NO. 1239-W