

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 22 1970
10-22-1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-20325-00-00

Operator's Full Name Aspen Resources LTD.
Complete Address 710 One Twenty Bldg., Wichita, Kansas 67202
Lease Name Steeples Well No. 1
Location NW SE NE Sec. 13 Twp. 9 Rge. (E) (W) 20
County Rooks Total Depth 3593'
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A XXX
Other well as hereafter indicated _____
Plugging Contractor Aspen Drlg.
Address Wichita, Kansas License No. _____
Operation Completed: Hour 5:45 P Day 20 Month 10 Year 1970

The above well was plugged as follows:

RTD 3593' 8 5/8 csg set at 250' cwc Cmt. Mat. 100 sk reg poz W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 10/22/70
INV. NO. 2728-W