

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

15-163-20003-00-00

FEB 1 1967
02-01-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Lahar of B & B Drilling Co. has this
date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Robert R. Price

Complete Address: 5727 East 43rd Street Tulsa, Oklahoma

Lease Name: Steeple Well No. 1

Location: SE SE NW Sec. 22 Twp. 9 Rge. 20 (E)(W) X

County Rooks Total Depth 3825' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lahar was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and displace
25 sc cement thru drill pipe. Heavy mud to 250' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug. 1/2 sc hulls and 8 sc cement to base pf cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Geo. F. Massey
Conservation Division Agent