



15-065-20254-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 22 1969  
CONSERVATION DIVISION  
Wichita, Kansas

9-22-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Clarence Michael of Sage Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Michael guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company,

Complete Address: 217 N. Water, Wichita, Kansas.

Lease Name: Lillie Gosselin Well No. 1-V

Location: NE-NE-NW, Sec. 10 Twp. 9 Rge. (E)(W) 21

County: Graham Total Depth 3693 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Michael was instructed to plug the well as follows:

251'--8 5/8" Surface casing, cement circulated .  
Top of Dakota section @ 525'.

Circulate hole with heavy mud. Pull DP to 740' and displace 100 Sx.  
cement. Pull DP to 240' and displace 20 Sx. cement thru DP. Pull DP,  
set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

*W. L. Nichols*  
Conservation Division Agent