



15-065-20282-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1969
CONSERVATION DIVISION
Wichita, Kansas

12-2-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Vic. Justus of Leben Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Justus guarantees payment of the plugging fee.

Operator's full Name: Tilco et al.

Complete Address: 200 Sutton Place, Wichita, Kansas.

Lease Name: Desair Well No. 1

Location: NE-SW-NE Sec. 10 Twp. 9 Rge. (E)(W) 21

County: Graham Total Depth 3780' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Justus was instructed to plug the well as follows:

243'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 550'.

Circulate hole with heavy mud. Pull DP to 775' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

K. L. Nichols
Conservation Division Agent