

State of Kansas



15-065-20689-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 P. O. Box 17027 3830 S. Meridian  
 WICHITA, KANSAS 67217

RECEIVED  
 STATE CORPORATION COMMISSION

APR 2 - 1974

CONSERVATION DIVISION  
 Wichita, Kansas

4-2-74

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. John Wright of Continental Oil Company has this date requested permission to plug the following described well:

Mr. Wright guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Company,

Complete Address: Box #267, Great Bend, Kansas.

Lease Name: E. Clack Well No. 4

Location: 2090' FSL & 2310' FWL Sec. 10 Twp. 9 Rge. (E)(W) 21

County: Graham Total Depth 3736' Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Wright was instructed to plug the well as follows:

241'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 625'.

Circulate hole with heavy mud. Pull DP to 850' and displace 110 Cu. Ft. cement thru DP. Pull DP to 250' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

*M. L. Nichols*

Conservation Division Agent