

KANSAS

4
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 2 1968
CONSERVATION DIVISION
Wichita, Kansas
5-2-68

13-163-20106-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Three G Oil, Inc.,

Complete Address: 1101 Wichita Plaza Wichita, Kansas

Lease Name McConchie Well No. 1

Location SW SW SE Sec. 15 Twp. 9 Rge. 18 (E) (W) X

County Rooks Total Depth 3360'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: H - 30, Inc.,

Address: Wichita, Kansas License No.

Operation Completed: Hour 6:30 P Day 30 Month 4 Year 1968

The Above well was plugged as follows:

RTD 3360' 8 5/8 csg set at 208' cwc 150 sc. Cem. Mat. 100 sc 6% 50-50 poz cement.
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cem.
thru drill pipe. Heavy mud-to 180' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: B. F. Messing
Well Plugging Supervisor

DATE 5/2/68

INV. NO. 7677-4